

NOTES:

1. SCOPE

PIPELINES INCLUDED UNDER THESE SPECIFICATIONS ARE THOSE INSTALLED TO CARRY STEAM, WATER OR ANY NON-FLAMMABLE SUBSTANCE WHICH FROM ITS NATURE OR PRESSURE, MIGHT CAUSE DAMAGE IF ESCAPING ON OR IN THE VICINITY OF SCRRRA PROPERTY. ADDITIONAL PIPELINES COVERED UNDER THESE STANDARDS INCLUDE SMALL DIAMETER PIPES USED TO INSTALL OR PROTECT FIBER OPTIC SYSTEMS AND TELECOMMUNICATION LINES. THESE STANDARDS SHALL BE USED IN CONJUNCTION WITH THE SCRRRA DESIGN CRITERIA MANUAL, CHAPTER 9, UTILITIES, AND THE AREMA MANUAL OF RAILWAY ENGINEERING CHAPTER 1, PART 5.

2. GENERAL REQUIREMENTS

- a. PIPELINES UNDER SCRRRA TRACKS AND ACROSS SCRRRA RIGHTS-OF-WAY SHALL BE ENCASED IN A LARGER PIPE OR CONDUIT CALLED THE CASING PIPE AS INDICATED IN FIGURE 1. EXCEPTION MAY BE GRANTED ON CASE BY CASE BASIS FOR NON-PRESSURE PIPELINE.
- b. CASING PIPE AND NON-CASED PIPELINES SHALL BE DESIGNED TO CARRY COOPER'S E-80 RAILROAD LIVE LOADING WITH DIESEL IMPACT FACTOR AS PER AREMA.
- c. PIPELINES SHALL BE LOCATED, WHERE PRACTICABLE, TO CROSS TRACKS AT APPROXIMATELY RIGHT ANGLES BUT PREFERABLY AT NO LESS THAN 45 DEGREES AND SHALL NOT BE PLACED WITHIN CULVERTS NOR UNDER RAILWAY BRIDGES.
- d. TEST BORING OR OTHER SOIL INVESTIGATIONS, APPROVED BY SCRRRA SHALL BE MADE, TO DETERMINE THE NATURE OF THE UNDERLYING MATERIAL FOR ALL PIPELINES WITH SIZES EQUAL OR GREATER THAN 48 INCHES IN DIAMETER AND A DEPTH FROM TOP OF PIPE TO BASE OF RAIL BETWEEN FIVE FEET SIX INCHES AND TEN FEET. THE TEST BORING SHOULD BE MADE ON THE CENTERLINE OF THE PIPE NEAR THE END OF THE BALLAST SECTION (IF POSSIBLE) ON EACH SIDE OF THE TRACKS AND AS DEEP AS THE BOTTOM OF THE BORE.
- e. EXCEPTION TO ANY DESIGN, CONSTRUCTION, LOCATION OR SPECIFICATIONS CONTAINED IN THIS STANDARD MUST BE AUTHORIZED BY SCRRRA. REQUESTS FOR EXCEPTIONS WILL BE CONSIDERED ONLY WHERE IT IS SHOWN THAT EXTREME HARDSHIP AND/OR UNUSUAL CONDITIONS PROVIDE JUSTIFICATION AND WHERE ALTERNATE MEASURES CAN BE USED IN KEEPING WITH THE INTENT OF THIS STANDARD. ALL REQUESTS FOR EXCEPTIONS SHALL BE FULLY DOCUMENTED WITH DESIGN DATA, CALCULATIONS, COST COMPARISONS AND OTHER PERTINENT INFORMATION.
- f. ALL PIPELINES SHALL BE PROMINENTLY MARKED BY SIGNS OR MARKERS (MAINTAINED BY OWNER) LOCATED OVER THE PIPE.

3. CARRIER PIPE

- a. CARRIER LINE PIPE AND JOINTS SHALL BE OF ACCEPTED MATERIAL AND CONSTRUCTION AS APPROVED BY THE SCRRRA DIRECTOR OF ENGINEERING AND CONSTRUCTION. JOINTS FOR CARRIER LINE PIPE OPERATING UNDER PRESSURE SHALL BE MECHANICAL OR WELDED TYPE. THE PIPE SHALL BE LAID WITH SUFFICIENT SLACK SO THAT IT IS NOT IN TENSION.
- b. CARRIER PIPES SHALL BE MANUFACTURED IN ACCORDANCE WITH THE FOLLOWING STANDARDS AND SPECIFICATIONS:
 - A. STEEL PIPE - ASTM OR API.
 - B. DUCTILE IRON PIPE - ANSI A21.51/AWWA C151, CLASS 56.
 - C. REINFORCED CONCRETE PIPE - ASTM C76, MINIMUM OF CLASS III(3000 D) RCP IS ACCEPTABLE WITHOUT CASING FOR LONGITUDINAL PIPE LOCATED 45 FEET OR MORE FROM THE CENTERLINE OF THE NEAREST TRACK.
 - D. VITRIFIED CLAY PIPE - ASTM C700.
 - E. PVC PLASTIC PIPE - ASTM D1784, MINIMUM SCHEDULE 40 PIPE.
 - F. HIGH DENSITY POLYETHYLENE (HDPE) SOLID WALL PIPE - ASTM D1248.
 - G. SEE AREMA CHAPTER 1, SECTION 5.2 FOR NON-FLAMMABLE GAS PIPE LINES.

4. CASING PIPE

- a. CASING PIPE AND JOINTS SHALL BE OF STEEL AND LEAK PROOF CONSTRUCTION, CAPABLE OF AREMA (COOPER E-80 LIVE LOAD) AND HAVE A SPECIFIED MINIMUM YIELD STRENGTH OF AT LEAST 35,000 PSI. THE INSIDE DIAMETER OF THE CASING PIPE SHALL BE AT LEAST TWO INCHES GREATER THAN THE LARGEST OUTSIDE DIAMETER OF THE CARRIER PIPE, JOINTS OR COUPLINGS FOR CARRIER PIPE LESS THAN SIX INCHES IN DIAMETER; AND AT LEAST FOUR INCHES GREATER FOR CARRIER PIPE SIX INCHES AND OVER IN DIAMETER. IN ALL CASES THE SPACE PROVIDED SHALL BE ADEQUATE TO ALLOW FOR REMOVAL WITHOUT DISTURBING THE CASING PIPE OR ROADBED.
- b. TABLE 1 INDICATES A MINIMUM THICKNESS BASED UPON SUPERIMPOSED LOADS ONLY AND IT IS THE RESPONSIBILITY OF THE LICENSEE AND/OR THE INSTALLER TO PROVIDE A CASING WHICH IS ADEQUATE FOR THE LOADS THAT RESULT DURING INSTALLATION. THE WALL THICKNESS MAY BE DECREASED BY 0.063 INCH, IF THE CASING IS INSTALLED WITH A PROTECTIVE COATING AND IS CATHODICALLY PROTECTED, EXCEPT FOR DIAMETERS UNDER 14 INCHES.
- c. CASING PIPE UNDER SCRRRA TRACKS AND ACROSS SCRRRA RIGHT-OF-WAY SHALL EXTEND THE GREATER OF THE FOLLOWING DISTANCES, MEASURED AT RIGHT ANGLE TO CENTERLINE OF TRACK. IF ADDITIONAL TRACKS ARE CONSTRUCTED IN THE FUTURE, THE CASING SHALL BE EXTENDED AT THE LICENSEE'S EXPENSE.
 - A. ACROSS THE ENTIRE WIDTH OF THE SCRRRA RIGHT-OF-WAY.
 - B. THREE FEET BEYOND THE DITCH LINE.
 - C. TWO FEET BEYOND THE TOE OF SLOPE.
 - D. A MINIMUM DISTANCE OF 25 FEET FROM EACH SIDE OF THE CENTERLINE OF OUTSIDE TRACK WHEN CASING IS SEALED AT BOTH ENDS AND,
 - E. A MINIMUM DISTANCE OF 45 FEET FROM EACH SIDE OF THE CENTERLINE OF OUTSIDE TRACK WHEN CASING IS OPEN AT BOTH ENDS.
- d. THE DEPTH OF THE CASING SHALL NOT BE LESS THAN AS SHOWN IN FIGURE 1. HORIZONTAL DIRECTIONAL DRILLING OF A PIPELINE NOT CARRYING LIQUID SUBSTANCES AND HAVING A NOMINAL DIAMETER OF SIX INCHES OR LESS SHALL HAVE A MINIMUM COVER OF SIX FEET FROM BASE OF RAIL TO TOP OF PIPELINE. HORIZONTAL DIRECTIONAL DRILLING FOR ALL PIPELINES EXCEEDING SIX INCHES NOMINAL DIAMETER, OR FOR ANY NOMINAL DIAMETER PIPELINE CARRYING LIQUID SUBSTANCES SHALL HAVE A MINIMUM COVER FROM BASE OF RAIL TO TOP OF PIPELINE OF 12 FEET. INSTALLATION SHALL BE BY THE DRY BORE METHOD ONLY.

5. CONSTRUCTION

- a. CASING PIPE SHALL BE CONSTRUCTED AS TO PREVENT LEAKAGE OF ANY SUBSTANCE FROM THE CASING THROUGHOUT ITS LENGTH, EXCEPT AT ENDS. CASING SHALL BE INSTALLED AS TO PREVENT THE FORMATION OF A WATERWAY UNDER THE ROADBED, AND WITH AN EVEN BEARING THROUGHOUT ITS LENGTH, AND SHALL SLOPE TO ONE END (EXCEPT FOR LONGITUDINAL OCCUPANCY).
- b. THE FACES OF ALL PITS (JACKING AND RECEIVING) SHALL BE LOCATED A MINIMUM OF 25 FEET FROM THE CENTERLINE OF THE NEAREST TRACK, MEASURED AT RIGHT ANGLES TO TRACK. SHORING, IF REQUIRED, SHALL MEET SCRRRA'S EXCAVATION SUPPORT GUIDELINES.
- c. FOR ALL PIPELINES WITH SIZES EQUAL OR GREATER THAN 48 INCHES, RAIL ELEVATIONS OVER THE WORK MUST BE MONITORED AT INTERVALS PRESCRIBED BY SCRRRA TO DETECT ANY TRACK MOVEMENT. MOVEMENTS OVER 1/4" VERTICALLY SHALL BE IMMEDIATELY REPORTED TO SCRRRA. SCRRRA WILL SURFACE THE TRACK SEVERAL TIMES IN ONE YEAR IF THERE IS ANY MOVEMENT AT LICENSEE AND/OR INSTALLER'S COST.
- d. THE METHOD OF CONSTRUCTION SHALL MEET ALL CURRENT AREMA AND "GREEN BOOK" SPECIFICATIONS AND REQUIREMENTS.
- e. THE BORING, TUNNELING OR JACKING OPERATION SHALL BE PROGRESSED ON A 24 HOUR BASIS WITHOUT STOPPAGE WHEN THE CASING IS 20 FEET FROM THE CENTERLINE OF THE NEAREST TRACK.
- f. THE BORING, TUNNELING OR JACKING INSTALLATION SHALL HAVE A BORED HOLE DIAMETER ESSENTIALLY THE SAME AS THE OUTSIDE DIAMETER OF THE PIPE PLUS THE THICKNESS OF THE PROTECTIVE COATING. IF VOIDS SHOULD DEVELOP OR IF THE BORED HOLE DIAMETER IS GREATER THAN THE OUTSIDE DIAMETER OF THE PIPE (INCLUDING COATING) BY MORE THAN APPROXIMATELY 1 INCH, THE SPACE SHALL BE FILLED BY GROUTING OR OTHER REMEDIAL MEASURES TAKEN AS APPROVED BY SCRRRA.
- g. THE BORE AND JACK METHOD (PUSHING PIPE INTO THE EARTH WITH A BORING AUGER ROTATING WITHIN PIPE TO REMOVE SPOIL) IS ACCEPTABLE.
- h. JACKING METHOD (PUSHING SECTIONS OF PIPE INTO POSITION WITH JACKS PLACED AGAINST A BACKSTOP AND EXCAVATION PERFORMED BY HAND FROM WITHIN THE JACKING SHIELD AT THE HEAD OF THE PIPE) IS ACCEPTABLE. IMMEDIATELY AFTER COMPLETION OF JACKING OPERATION, THE INSTALLATION SHALL BE PRESSURE GROUTED.
- i. TUNNELING METHOD (PLACING RINGS OF LINER PLATE WITHIN THE TAIL SECTION OF A TUNNELING SHIELD OR TUNNELING MACHINE) IS ACCEPTABLE. TUNNELING SHALL NOT BE CONSIDERED WHERE LESS THAN SIX FEET OF COVER EXISTS OR WHERE EXCESSIVELY SANDY, LOOSE OR ROCKY SOILS ARE ANTICIPATED.
- j. HORIZONTAL DIRECTIONAL DRILLING METHOD (BORING A SMALL DIAMETER PILOT HOLE ON A DESIRED VERTICAL AND HORIZONTAL ALIGNMENT USING A CUTTING HEAD WITH VISCOUS SLURRY AND PULLING A PIPE WITH A REAMER) IS ACCEPTABLE.
- k. PIPE RAMMING METHOD (PUSHING A SOLID STEEL ROD UNDER THE ROADBED, ATTACHING A CONE SHAPED EXPANDER TO THE END OF THE ROD, ATTACHING A CASING PIPE TO THE EXPANDER AND PULLING BACK THE ROD) IS NOT ACCEPTABLE.
- l. THE USE OF WATER JETTING TO FACILITATE CASING PLACEMENT AND SPOIL REMOVAL IS NOT PERMITTED.
- m. JACKING, BORING, OR TUNNELING PIPES EQUAL TO OR GREATER THAN 48 INCHES NOMINAL DIAMETER WILL NOT BE ALLOWED WITH LESS THAN ONE AND ONE HALF TIMES THE PIPES NOMINAL DIAMETER OF COVER FROM BASE OF RAIL TO TOP OF PIPELINE.
- n. JACKING AND BORING OF PIPELINES WITH A NOMINAL DIAMETER GREATER THAN 72 INCHES SHALL NOT BE ALLOWED UNLESS OTHERWISE APPROVED BY SCRRRA.

6. SEALS AND SUPPORTS

THE ENDS OF CASING ARE TO BE SUITABLY SEALED AGAINST THE ENTRANCE OF FOREIGN MATERIAL, BUT ARE NOT TO BE TIGHTLY SEALED. ALL SUPPORTS, INSULATORS AND CENTERING DEVICES FOR THE CARRIER PIPE SHALL BE SO DESIGNED AND CONSTRUCTED THAT NO LOADS FROM THE ROADBED, TRAFFIC OR CASING PIPE ITSELF ARE TRANSMITTED TO CARRIER PIPE. THE SPACING OF SUCH SUPPORTS LONGITUDINALLY SHALL NOT BE GREATER THAN TEN FEET.

7. SHUT-OFF VALVES

ACCESSIBLE EMERGENCY SHUT-OFF VALVES SHALL BE INSTALLED WITHIN EFFECTIVE DISTANCES EACH SIDE OF THE TRACK AS MUTUALLY AGREED TO BY SCRRRA AND THE PIPELINE COMPANY. WHERE PIPELINES ARE PROVIDED WITH AUTOMATIC CONTROL STATIONS AT LOCATIONS AND WITHIN DISTANCES APPROVED BY SCRRRA DIRECTOR OF ENGINEERING AND CONSTRUCTION, NO ADDITIONAL VALVES SHALL BE REQUIRED. SHUT-OFF VALVES ON SCRRRA RIGHT-OF-WAY SHOULD BE AVOIDED.

8. LONGITUDINAL PIPELINES


PIPELINES LAID LONGITUDINALLY ON SCRRRA RIGHT-OF-WAY SHALL BE LOCATED AS FAR AS PRACTICABLE FROM ANY TRACKS OR OTHER IMPORTANT STRUCTURES AND AS CLOSE TO THE RAILROAD PROPERTY LINE AS POSSIBLE. IF LOCATED WITHIN 25 FEET OF THE CENTERLINE OF ANY TRACK OR WHERE THERE IS DANGER OF DAMAGE TO ANY BRIDGE, BUILDING OR STRUCTURE, THE CARRIER PIPE SHALL BE ENCASED OR OF SPECIAL DESIGN AS APPROVED BY SCRRRA DIRECTOR OF ENGINEERING AND CONSTRUCTION. PIPELINES SHALL BE BURIED NOT LESS THAN FOUR (4) FEET FROM THE GROUND SURFACE TO THE TOP OF THE PIPE.

9. APPROVAL OF PLANS

SCRRRA'S RIGHT-OF-WAY ENCROACHMENT APPLICATION, PLAN REVIEW FEES, AND PLANS FOR PROPOSED INSTALLATION SHALL BE SUBMITTED TO SCRRRA FOR APPROVAL PRIOR TO CONSTRUCTION. PLANS SHALL BE DRAWN TO SCALE SHOWING THE RELATION OF THE PROPOSED PIPELINE TO SCRRRA TRACKS, ANGLE OF CROSSING, LOCATION OF VALVES, SCRRRA SURVEY STATION, RIGHT-OF-WAY LINES AND GENERAL LAYOUT OF TRACKS AND SCRRRA FACILITIES. PLANS SHOULD ALSO SHOW A CROSS SECTION (OR SECTIONS) FROM FIELD SURVEY, SHOWING PIPE IN RELATION TO ACTUAL PROFILE OF GROUND AND TRACKS. ADDITIONAL INFORMATION ON APPROVAL PROCESSES AND REQUIREMENTS ARE AVAILABLE ON SCRRRA'S WEBSITE AT WWW.METROLINKTRANS.COM.

10. EXECUTION OF WORK



THE PIPELINE REAL ESTATE AGREEMENT AND SCRRRA'S TEMPORARY RIGHT-OF-ENTRY AGREEMENT (SCRRRA FORM NO. 36) SHALL BE FULLY EXECUTED BEFORE ANY WORK WILL BE ALLOWED ON SCRRRA RIGHT-OF-WAY. THE EXECUTION OF WORK ON SCRRRA RIGHTS-OF-WAY, INCLUDING THE SUPPORTING OF TRACKS, SHALL BE SUBJECT TO THE INSPECTION AND DIRECTION OF SCRRRA RIGHT-OF-WAY ENGINEER OR HIS/HER AUTHORIZED REPRESENTATIVE. THE INSTALLER SHALL PERFORM THE CONSTRUCTION OR MAINTENANCE WORK IN SUCH A MANNER AND AT SUCH TIMES AS SHALL NOT ENDANGER OR INTERFERE WITH SCRRRA'S OPERATIONS, INCLUDING RELATION TO THE PROPER MANNER OF PROTECTING THE TRACKS, SIGNALS, FIBER OPTIC CABLES, PIPELINES, OTHER PROPERTY AND TENANTS OR LICENSEES AT OR IN THE VICINITY OF THE WORK DURING THE PERIOD OF CONSTRUCTION.



CASING REQUIREMENTS - FIGURE 1

TABLE 1

STEEL CASING (UNCOATED AND UNPROTECTED)			
NOMINAL DIAMETER (INCHES)	MIN. WALL THICKNESS (INCHES)	NOMINAL DIAMETER (INCHES)	MIN. WALL THICKNESS (INCHES)
14" & UNDER	0.250" (1/4")	44" & 46"	0.656" (21/32")
16"	0.281" (9/32")	48"	0.688" (11/16")
18"	0.312" (5/16")	50"	0.719" (23/32")
20" & 22"	0.344" (11/32")	52"	0.750" (3/4")
24"	0.375" (3/8")	54"	0.781" (25/32")
26"	0.406" (13/32")	56" & 58"	0.812" (13/16")
28"	0.438" (7/16")	60"	0.844" (27/32")
30"	0.469" (15/32")	62"	0.875" (7/8")
32"	0.500" (1/2")	64"	0.906" (29/32")
34" & 36"	0.531" (17/32")	66" & 68"	0.938" (15/16")
38"	0.562" (9/16")	70"	0.969" (31/32")
40"	0.594" (19/32")	72"	1.000" (1")
42"	0.625" (5/8")	OVER 72"	MUST BE APPROVED BY SCRRRA

DRAWN BY: A. CARLOS		DATE: 03/31/2011	
 ASSISTANT DIRECTOR- STANDARDS & DESIGN			
 DIRECTOR OF ENGINEERING AND CONSTRUCTION			
X	XX-XX-XX	REVISION	XX XX
REV.	DATE	DESCRIPTION	DES. ENG.

SCRRRA ENGINEERING STANDARDS ARE INTENDED FOR SCRRRA APPROVED USES ONLY. FOR NON-SCRRRA APPROVED USES, SCRRRA SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF THE DATA OR INFORMATION CONTAINED HEREIN. THE SELECTION AND USE OF THESE STANDARDS IS THE SOLE RESPONSIBILITY OF THE USER AND SHOULD NOT BE USED WITHOUT CONSULTING A REGISTERED PROFESSIONAL ENGINEER. ALL WARRANTIES AND REPRESENTATIONS OF ANY KIND ARE DISCLAIMED. ANYONE MAKING USE OF THIS INFORMATION AGREES THAT IT ASSUMES ALL LIABILITY ARISING FROM SUCH USE. NO PART OF THESE STANDARDS SHOULD BE REPRODUCED OR DISTRIBUTED IN ANY FORM OR BY ANY MEANS WITHOUT THE PRIOR WRITTEN PERMISSION OF SCRRRA. ALL RIGHTS RESERVED.



SOUTHERN CALIFORNIA REGIONAL RAIL AUTHORITY
ONE GATEWAY PLAZA, 12TH FLOOR, L. A., CA. 90012

ENGINEERING STANDARDS		STANDARD
PIPE LINES		5001
FOR NON - FLAMMABLE SUBSTANCES		SCALE: NTS
ACROSS OR ALONG RIGHT OR WAY		REVISION SHEET
		1 OF 1
		CADD FILE: ES5001